

ADDENDUM NO. 1

---

PROJECT: **ADDITION TO THE BLUEBERRY PAVILION  
WILMOT ORCHARDS, 3377 CONCESSION RD. 3, CLARINGTON, ONTARIO  
PROJECT NO. 19.316**

DATE: June 5, 2020

The following information supplements and/or supersedes the drawings and specifications, issue date May 14, 2020 for Permit & Pricing.

This Addendum forms part of the contract documents and is to be read, interpreted, and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named projects to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by making written reference to it.

REFER TO: **ARCHITECTURAL CLARIFICATIONS**

1. Refer to Supplements to Bid Form.
- 1.1. In Section 2, Alternative Prices, include in scope of work full coverage of self-adhering roofing underlay, PE200HT High Temperature Roof Underlay by Henry, or equivalent product by Grace.
- 1.2. In addition to Bid Form and Supplements to Bid Form, Bidders are to submit with their bids, product literature (brochures and/or catalogue excerpts) for window and door products included within their scope of work. No specific products or brands have been identified or endorsed, either on drawings or in specifications, or during bidding period.
2. Refer to Exterior Elevations and Sections on drawings A201 and A301.
- 2.1. Helical foundation piles shown are illustrative of approximate location and quantity required and are not indicating required depth of piles. Contractors are required to include and account for in scope of work, likely required depth of piles.
- 2.2. Windows W1 to W8 are casement windows. Middle muntin bar is fixed.
- 2.3. Refer to Door Schedule. Four-panel doors 108g and 108h are to stack at one end.
3. There is no civil or mechanical work required in scope of work for this project.
4. Electrical scope of work is as shown on architectural drawings and Responsibility Schedule; receptacles, light switches, LED light fixtures, emergency lighting and exit signs, installation of owner-supplied pendant fixtures, and associated distribution wiring.

**END OF ADDENDUM NO. 1**