

Project: **New Fire Station No. 1**
RFT# T-FD-22-01
Highlands Boulevard, Millbrook, ON

Date: June 08, 2022
Owner: Township of Cavan Monaghan
Greenview File: 164.21.005

This Addendum forms part of the Tender Documents and shall supersede all prior issued tender documentation and/or Addenda as noted, and specifically applicable.

This Addendum consists of 2 page(s), and no attachments.

1. Project Manual:

- .1 Section 00 41 13 Tender Forms.
 - .1 Appendix C – Alternatives:
 - .1 Alternative 1, Description, add:
 - .1 “Owner would complete all Owner-specific pre-excavation utility clearance requirements, demarcations, light duty silt fence installations at both excavation and disposal locations, and related responsibilities, reserved to the Owner’s specific work in this regard.”
 - .2 “Construction entrance off County Road 10 will not be developed by Owner under noted alternative. All work by Owner restricted to areas west of County Road 10.”
 - .3 “Any all work performed by Owner shall be represented by the Owner’s independent warranty requirements/conditions.”
- .2 Section 01 21 00 Allowances.
 - .1 Part 1.3.7.2, add:
 - .1 “.5 Personal Locker Units in Men’s Washroom Room 108 and Women’s Washroom Room 109.”
- .3 Section 04 30 00 Unit Masonry.
 - .1 Part 2.2.1, add:
 - .1 “.3 Approved equivalent manufacturers.”
- .4 Section 07 61 00 Sheet Metal Roofing.
 - .1 Part 2.3.2, add word “minimum” after “26 ga”.
- .5 Attachment – Geotechnical Report(s).
 - .1 Add, “Footings and foundations walls should be backfilled with non-frost susceptible granular material such as Granular “B”, type 1 as per OPSS 1010.”

2. Drawings:

- .1 Drawing 000 – Construction Assemblies.
 - .1 Roof Assembly 441:
 - .1 For assembly note, “26 GAUGE STANDING SEAM ROOFING...”, add “MIN.” after the word “GAUGE”.

- .2 Roof (Canopy) Assembly 451:
 - .1 For assembly note, "1½" 26 GAUGE PRE-FINISHED SOFFIT PANEL.", add "MIN." after the word "GAUGE".

End of Addendum 03